

ARIZONA DEPARTMENT OF TRANSPORTATION

ADVERTISEMENT FOR BIDS

BID OPENING: (FRIDAY, JULY, 25, 2008), AT 11:00 A.M. (M.S.T.)

TRACS NO	092 CH 328 H459601C
PROJ NO	STP-092-A(001)B
TERMINI	SIERRA VISTA- BISBEE HIGHWAY (SR92)
LOCATION	CARR CANYON RD.- HUNTER CANYON

ROUTE NO.	MILEPOST	DISTRICT	ITEM NO.
SR92	328.06 to 332.04	SAFFORD	12904

The amount programmed for this contract is \$16,842,000. The location and description of the proposed work and the representative items and approximate quantities are as follows:

The proposed work is located in Cochise County along a section of SR 92 beginning just north of Carr Canyon Road (MP 328.06) and extending southerly approximately four miles to just south of Hunter Canyon (MP 332.04). The project encompasses widening the existing roadway to a five-lane section with two through lanes in each direction and a continuous center two-way left-turn lane. The work consists of both pavement widening and reconstructing portions of the roadway in rural and urban sections which includes the following work: roadway excavation, furnishing and placing aggregate base, asphaltic concrete, concrete curb and gutter, traffic signal, detention basin excavation and construction, extending and constructing box and pipe culverts, installing storm drain system, signing and marking, and other related work.

REPRESENTATIVE ITEMS	UNIT	QUANTITY
Removal of AC Pavement	SQ.YD	29,517
Removal of Pipe	L.FT.	2,032
Remove Guard Rail	L.FT	3,775
Remove Fence	L.FT.	5,308
Excavation	CU.YD.	103,678
Furnish Water	M.GAL.	20,000
Aggregate Base, Class 2	CU.YD.	24,393
Asphalt Binder(PG 64-22)	TON	2,315
ACFC (Asphalt-Rubber)	TON	4,162
Asphalt Rubber Material (For AR-ACFC)	TON	375
AC(3/4 " Mix)(End Product)(Special Mix)	TON	45,388
Pipe	L.FT.	4,604
Concrete Catch Basin	EACH	16
Metal Hand Rail	L.FT.	1364
Structural Concrete(Class S) (F'C=3000)	CU.YD.	2,362
Reinforcing Steel	LB.	302,560
Pavement Marking (Thermoplastic)	L.FT.	164,784
Pavement Marker, Raised	EACH	2107
Pole(Type A/G/Q/R)	EACH	24

Mast Arm	EACH	22
Conductor	L.FT.	9,140
Control Cabinet (Type IV)	EACH	1
Video Detection System(4-Camera)	L.SUM	1
Seeding (Class II)	ACRE	40
Fence	L.FT.	8,736
Concrete Curb and Gutter	L.FT.	6,009
Concrete Sidewalk and Driveway	SQ.FT.	3,185
Riprap	CU.YD.	8,245
Retaining Wall (B18.10)	SQ.FT.	898
Concrete Channel Lining(6")	SQ.YD.	270
Median Paving (Decorative)	SQ.YD.	699
Provide On-The-Job Training	HOUR	2,000
Contractor Quality Control	L.SUM	1
Construction Surveying and Layout	L.SUM	1

The time allowed for the completion of the work included in this project will be 390 working days.

The Arizona Department of Transportation hereby notifies all bidders that pursuant to this advertisement for bids, Disadvantaged Business Enterprises will be afforded full opportunity to submit bids in response to this solicitation and will not be discriminated against on the grounds of race, color, sex, or national origin in consideration for an award.

Project plans, special provisions, and proposal pamphlets may be purchased from Contracts and Specifications Section, 1651 W. Jackson, Room 121F, Phoenix, AZ 85007-3217, (602) 712-7221. Plans and bidding documents should be available for sale to bidders within one week following the advertisement for bids. The cost is \$101.00, payable at time of order by cash, check or money order. Please indicate whether a bid proposal package or a subcontractor/supplier set is desired. An additional fee of \$5.00 will be charged for each set of Special Provisions requested which is not accompanied by the purchase of a related set of project plans. Checks should be made payable to the Arizona Department of Transportation. No refund will be made for plans and specifications returned. We cannot guarantee mail delivery.

This project is eligible for electronic bidding.

One CD containing cross sections and the earthwork report and a second CD containing the geotechnical investigation report are available for sale at Contracts and Specifications. The cost of each CD is \$5.00, payable at time of order by cash, check or money order.

No contracting firm will be issued a proposal pamphlet until it has become prequalified. The Application for Contractor Prequalification shall be filed at least 15 calendar days prior to the bid opening date. The Application may be obtained from Contracts and Specifications Section.

No award will be made to any contractor who is not a duly licensed contractor in accordance with Arizona Revised Statutes 32-1101 through 32-1170.03.

All labor employed on this project shall be paid in accordance with the minimum wage rates shown in the General Wage Decision. These rates have been determined in accordance with the requirements of the law and issued by the Secretary of Labor for this project. The wage scale is on file in Contracts and Specifications Section and copies may be obtained at all reasonable times.

A proposal guaranty in the form of either a certified or a cashier's check made payable to the State Treasurer of Arizona for not less than ten percent of the amount of the bid or in the form of a surety (bid) bond for ten percent of the amount of the bid shall accompany the proposal.

Surety (bid) bonds will be accepted only on the form provided by the Department and only from corporate sureties authorized to do business in Arizona.

Proposal pamphlets shall be submitted only in the envelope provided by the Department to:

Arizona Department of Transportation
Intermodal Transportation Division
Contracts and Specifications Section
1651 West Jackson Street, Room 121F
Phoenix, Arizona 85007-3217

Sealed bids will be received until the hour indicated and then publicly opened and read. No bids will be received after the time specified.

Engineering Specialist:	Rashidul Haque	(602)712-8261
Construction Supervisor:	Jackie P. Watson	(520) 459-5088

BARRY CROCKETT,
Engineer-Manager
Contracts & Specifications Section

092 CH 328 H459601C
STP-092-A(001)B
June 12,2008