

ARIZONA DEPARTMENT OF TRANSPORTATION

ADVERTISEMENT FOR BIDS

BID OPENING: FRIDAY, AUGUST 22, 2008, AT 11:00 A.M. (M.S.T.)

TRACS NO 060 MA 111 H595801C
PROJ NO 060-B(004)A
TERMINI PHOENIX-WICKENBURG HIGHWAY (US 60)
LOCATION MP 111.13 - MP 112.77

TRACS NO 060 MA 110 H700601C
PROJ NO 060-B-NFA
TERMINI PHOENIX-WICKENBURG HIGHWAY (US 60)
LOCATION MP 110.66 - MP 112.13

| ROUTE NO. | MILEPOST | DISTRICT | ITEM NO. |
|-----------|-----------------|----------|----------|
| US 60 | 110.13 - 112.77 | PRESCOTT | 17208 |
| US 60 | 110.66 - 112.13 | PRESCOTT | 17308 |

The amount programmed for this contract is \$7,525,000.00. The location and description of the proposed work and the representative items and approximate quantities are as follows:

The proposed projects are located within the Town of Wickenburg in Maricopa County on US 60, beginning at Milepost 110.66 and proceeding southeasterly to Milepost 112.77 for a distance of approximately 2.11 miles.

The project work consists of milling and replacing existing asphaltic concrete pavement, widening the four-lane highway to provide a continuous left turn lane, a right turn lane, an asphalt rubber-asphaltic concrete friction course, widening the existing Calamity Wash bridge, grading, drainage, pipe and box culvert extensions, removing existing guard rail and end terminals, constructing concrete barriers and impact attenuators on selected high fills, constructing curb and gutter, driveways and turnouts on each side of the widened roadway, construction and installation of a new potable water line and sanitary sewer line systems, and other related work.

| REPRESENTATIVE ITEMS | UNIT | QUANTITY |
|---|---------|----------|
| Removal of Trees | EACH | 5 |
| Removal of Str. Concrete | CU. YD. | 182 |
| Removal of Concrete Curb and Gutter | L.FT | 160 |
| Removal of Conc. Sidewalks, Driveways & Slabs | SQ.FT | 3,674 |
| Removal of Asph. Conc. Pave. (For Roadway Widen.) | SQ.FT | 23,030 |
| Removal of Asph. Conc. Pave (Existing Driveways) | SQ.FT | 1,032 |
| Remove Guard Rail | L.FT. | 5,333 |
| Remove Bituminous Pavement (Mill. 2" & 3") | SQ.YD | 53,744 |
| Saw Cutting | L.FT. | 17,946 |
| Roadway Excavation | CU. YD. | 27,690 |
| Furnish Water | M. GAL. | 5,800 |
| Aggregate Base, Class 2 | CU. YD | 2,444 |
| Drainage Excavation | CU. YD | 100 |
| Structural Excavation | CU. YD | 2,408 |
| Structural Backfill | CU. YD | 1,045 |
| Bituminous Tack Coat | TON | 40 |

| | | |
|---|-----------|---------|
| Asphalt Binder (PG 76-16) | TON | 600 |
| Asphaltic Conc.(3/4" mix) | TON | 11,615 |
| Asphaltic Conc.(Misc. Structural)(Driveways) | TON | 39 |
| Asphalt Concrete Friction Course (Asphalt-Rubber) | TON | 2,468 |
| Asphalt Rubber Material (For AR-ACFC) | TON | 222 |
| Pipe Corrugated Metal (24" & 36") | L.FT. | 2,550 |
| Concrete Catch Basin | EACH | 16 |
| Str. Concrete (Class S) (F'C=3,000) | CU. YD | 590 |
| Str. Concrete (Class S) (F'C=3,500) | CU. YD | 331 |
| Str. Concrete (Class S) (F'C=4,500) | CU. YD | 129 |
| Reinforcing Steel | LB. | 158,922 |
| Temp. Conc. Barrier (Inst. & Removal) | L.FT. | 350 |
| Temp. Impact Attenuators (Inst. & Removal) | EACH | 2 |
| Temp. Pave. Marking (Stripe) | L.FT. | 27,883 |
| Obliterate Pavement Marking (Stripe) | L.FT. | 1,500 |
| Temp. Conc. Barrier (In-Use) | L.FT./DAY | 74,802 |
| Temp. Impact Attenuators (In-Use) | EACH-DAY | 260 |
| Barricade (Type ii, Vert. Panel, Tubular Marker) | EACH-DAY | 15,490 |
| Barricade (Type III, High Level Flag Trees) | EACH-DAY | 325 |
| Truck Mounted Attenuator | EACH-DAY | 135 |
| Temporary Sign (Less Than 10 S.F.) | EACH-DAY | 294 |
| Temporary Sign (Less Than 10 S.F.) | EACH-DAY | 7,042 |
| Seeding (Class II) | ACRE | 12 |
| Pipe, Ductile Iron (6" & 12", MAG Std.) | L.FT. | 1,303 |
| Sewer Pipe (4", & 10") (Ductile Iron) | L.FT. | 2,660 |
| Sewer Pipe (4", 6", & 8") (PVC) | L.FT. | 643 |
| Sewer Pipe (10") (Ductile Iron)(MAG Std. 750) | L.FT. | 200 |
| Sewer Pipe (8" PVC MAG Std. 745) | L.FT. | 1,560 |
| Erosion Control (RIPRAP) (D50=8") | CU. YD | 82 |
| Erosion Control | L.FT. | 19,466 |
| Concrete Curb (C-05.10)(Type D) | L.FT. | 16,780 |
| Concrete Driveway | SQ.FT | 11,515 |
| Scupper (9.5', 14' & 18.5'-23.0')(Detail 24) | EACH | 15 |
| Shotcrete (4") | SQ.YD | 670 |
| Retaining Wall | SQ.FT | 2936 |
| Contractor Quality Control | L.SUM | 1 |
| Construction Surveying and Layout | L.SUM | 1 |

The time allowed for the completion of the work included in these projects will be 215 working days.

The Arizona Department of Transportation hereby notifies all bidders that pursuant to this advertisement for bids, Disadvantaged Business Enterprises will be afforded full opportunity to submit bids in response to this solicitation and will not be discriminated against on the grounds of race, color, sex, or national origin in consideration for an award.

Project plans, special provisions, and proposal pamphlets may be purchased from Contracts and Specifications Section, 1651 W. Jackson, Room 121F, Phoenix, AZ 85007-3217, (602) 712-7221. Plans and bidding documents should be available for sale to bidders within one week following the advertisement for bids. The cost is \$94.00, payable at time of order by cash, check or money order. Please indicate whether a bid proposal package or a subcontractor/supplier set is desired. An additional fee of \$5.00 will be charged for each set of Special Provisions requested which is not accompanied by the purchase of a related set of project plans. Checks should be made payable to the Arizona Department of Transportation. No refund will be made for plans and specifications returned. We cannot guarantee mail delivery.

This project is eligible for electronic bidding.

Cross sections and/or earthwork quantity sheets, if available, may be ordered from the Control Desk of Roadway Design Section at (602) 712-8667. Orders must be placed at least five days prior to bid opening to insure availability. Documents may be picked up and paid for at Contracts & Specifications Section.

No contracting firm will be issued a proposal pamphlet until it has become prequalified. The Application for Contractor Prequalification shall be filed at least 15 calendar days prior to the bid opening date. The Application may be obtained from Contracts and Specifications Section.

No award will be made to any contractor who is not a duly licensed contractor in accordance with Arizona Revised Statutes 32-1101 through 32-1170.03.

All labor employed on this project shall be paid in accordance with the minimum wage rates shown in the General Wage Decision. These rates have been determined in accordance with the requirements of the law and issued by the Secretary of Labor for this project. The wage scale is on file in Contracts and Specifications Section and copies may be obtained at all reasonable times.

A proposal guaranty in the form of either a certified or a cashier's check made payable to the State Treasurer of Arizona for not less than ten percent of the amount of the bid or in the form of a surety (bid) bond for ten percent of the amount of the bid shall accompany the proposal.

Surety (bid) bonds will be accepted only on the form provided by the Department and only from corporate sureties authorized to do business in Arizona.

Proposal pamphlets shall be submitted only in the envelope provided by the Department to:

Arizona Department of Transportation
Intermodal Transportation Division
Contracts and Specifications Section
1651 West Jackson Street, Room 121F
Phoenix, Arizona 85007-3217

Sealed bids will be received until the hour indicated and then publicly opened and read. No bids will be received after the time specified.

| | | |
|--------------------------|-------------|-----------------------|
| Engineering Specialist: | Reza Jafari | (602) 712-7953 |
| Construction Supervisor: | Andrew Roth | (928) 759-2426 x 3624 |

BARRY CROCKETT,
Engineer-Manager
Contracts & Specifications Section