

ARIZONA DEPARTMENT OF TRANSPORTATION

ADVERTISEMENT FOR BIDS

BID OPENING: FRIDAY, OCTOBER, 26, 2007, AT 11:00 A.M. (M.S.T.)

TRACS NO 008 YU 029 H524001C
PROJ NO IM-008-A(201)A
TERMINI YUMA-CASA GRANDE HIGHWAY, I-8
LOCATION ADONDE RD – MOHAWK CANAL

ROUTE NO.	MILEPOST	DISTRICT	ITEM NO.
I-8	29.01 to 37.09	YUMA	16808

The amount programmed for this contract is \$13,540,000.00. The location and description of the proposed work and the representative items and approximate quantities are as follows:

The proposed pavement preservation project is located in Yuma County on Interstate 8, between MP 29.01 to 37.09. It is about 30 miles east of Yuma in Wellton area. The proposed work consists of milling and replacing the existing AC and AR-ACFC, improvements of bridges, grade separation of Asher road, shoulder buildup, installation of guardrail, pavement markings, pipe lining and other related work.

REPRESENTATIVE ITEMS	UNIT	QUANTITY
Removal of Structural Concrete	CU.YD.	16
Removal of Embankment Curb	L.FT.	5,892
Remove of Pipe	L.FT.	198
Removal of Bitum. Pavement (Mill.) (Var. Depths)	SQ.YD.	4,03,706
Remove Guard Rail	L.FT.	4,588
Remove Fence	L.FT.	46,876
Remove Cattle Guards	EACH	4
Remove (Trees) (Mechanised)	EACH	15
Remove (Down Drain Inlet)	EACH	12
Shoulder Build-up	L.FT.	149,000
Bituminous Tack Coat & Fog Coat	TON	392
Asphalt Binder (PG 76-16)	TON	4,267
Asphaltic Concrete Friction Course(Asphalt Rubber)	TON	8,011
Asphalt Rubber Material (For AR-ACFC)	TON	721
Asphalt Concrete(3/4" Mix)(End Product)(Sp. Mix)	TON	85,337
Pipe, Corrugated Metal, 24" to 36"	L.FT.	128
Flared End Section 18" to 36" (Pipe Culvert)	EACH	52
Structural Concrete (Class S)(F'C = 4,000)	CU.YD.	65
Reinforcing Steel (Epoxy Coated)	LB.	5,039
Temporary Concrete Barrier(Installation & Removal)	L.FT.	1,600
Temporary Impact Attenuators (Inst. & Removal)	EACH	4
Temporary Painted Marking (Stripe)	L.FT.	221,000
Temporary Concrete Barrier (In Use)	L.FT./Day	22,400
Temporary Impact Attenuators (In-Use)	EACH/Day	56

Truck Mounted Attenuator	EACH-DAY	188
Flagging Services (Civilian)	HOUR	1,360
Delineator (Flexible) (Single or Double)	EACH	464
Permanent Pavement Marking (Painted)(White & Y)	L.FT.	345,346
Pavement Marker (Raised Type DR Yellow/Red)	EACH	4,273
Seeding (Class II)	ACRE	35
Barbed Wire Fence, (Type 2)	L.FT.	45,876
Guard Rail, W-Beam, Single Face	L.FT.	6,350
Guard Rail Terminal (Tangent Type)	EACH	32
Thrie-Beam Guard Rail Transition System	EACH	16
Embankment Curb	L.FT.	5,958
Contractor Quality Control	L.SUM	1
Construction Surveying And Layout	L.SUM	1
Ground-In Rumble Strip (12 Inch)	L.FT.	94,266

The time allowed for the completion of the work included in this project will be 135 working days.

The Arizona Department of Transportation hereby notifies all bidders that pursuant to this advertisement for bids, Disadvantaged Business Enterprises will be afforded full opportunity to submit bids in response to this solicitation and will not be discriminated against on the grounds of race, color, sex, or national origin in consideration for an award.

Project plans, special provisions, and proposal pamphlets may be purchased from Contracts and Specifications Section, 1651 W. Jackson, Room 121F, Phoenix, AZ 85007-3217, (602) 712-7221. Plans and bidding documents should be available for sale to bidders within one week following the advertisement for bids. The cost is \$43.00, payable at time of order by cash, check or money order. Please indicate whether a bid proposal package or a subcontractor/supplier set is desired. An additional fee of \$5.00 will be charged for each set of Special Provisions requested which is not accompanied by the purchase of a related set of project plans. Checks should be made payable to the Arizona Department of Transportation. No refund will be made for plans and specifications returned. We cannot guarantee mail delivery.

This project is eligible for electronic bidding.

No contracting firm will be issued a proposal pamphlet until it has become prequalified. The Application for Contractor Prequalification shall be filed at least 15 calendar days prior to the bid opening date. The Application may be obtained from Contracts and Specifications Section.

No award will be made to any contractor who is not a duly licensed contractor in accordance with Arizona Revised Statutes 32-1101 through 32-1170.03.

All labor employed on this project shall be paid in accordance with the minimum wage rates shown in the General Wage Decision. These rates have been determined in accordance with the requirements of the law and issued by the Secretary of Labor for this project. The wage scale is on file in Contracts and Specifications Section and copies may be obtained at all reasonable times.

A proposal guaranty in the form of either a certified or a cashier's check made payable to the State Treasurer of Arizona for not less than ten percent of the amount of the bid or in the form of a surety (bid) bond for ten percent of the amount of the bid shall accompany the proposal.

Surety (bid) bonds will be accepted only on the form provided by the Department and only from corporate sureties authorized to do business in Arizona.

Proposal pamphlets shall be submitted only in the envelope provided by the Department to:

Arizona Department of Transportation
Intermodal Transportation Division
Contracts and Specifications Section
1651 West Jackson Street, Room 121F
Phoenix, Arizona 85007-3217

Sealed bids will be received until the hour indicated and then publicly opened and read. No bids will be received after the time specified.

Engineering Specialist:	Sarker Rahman	(602) 712-8262
Construction Supervisor:	Jaime Hernandez	(928) 317-2158

BARRY CROCKETT,
Engineer-Manager
Contracts & Specifications Section