

ARIZONA DEPARTMENT OF TRANSPORTATION

ADVERTISEMENT FOR BIDS

BID OPENING: THURSDAY, DECEMBER 13, 2007, AT 11:00 A.M. (M.S.T.)

TRACS NO 010 CH 356 H656601C
PROJ NO IM-010-F(200)A
TERMINI BENSON-STEINS PASS HWY (I-10)
LOCATION LUZENA-BOWIE (WB)

ROUTE NO.	MILEPOST	DISTRICT	ITEM NO.
I-10	356.47 to 362.60	SAFFORD	18308

The amount programmed for this contract is \$5,500,000.00. The location and description of the proposed work and the representative items and approximate quantities are as follows:

The proposed work is located in Cochise Country on the Benson – Steins Pass Highway (I-10, WB) between Luzena and Bowie. The project begins at Milepost 356.47 and proceeds easterly to Milepost 362.60. The project consists of milling of bituminous pavement in variable depths and replacing with AC and AR-ACFC, improvement of curve, removal and replacement of spillway and downdrain inlets, embankment curbs, guardrail, bridge rails; shoulder build-up, pavement markings, rumble strips, seeding and other related work.

REPRESENTATIVE ITEMS	UNIT	QUANTITY
Removal of Structural Concrete	CU.YD.	25
Removal of Embankment Curb	L.FT.	2,960
Removal of Bitum. Pavement (Mill.) (Var. Depths)	SQ.YD.	96,276
Remove & Salvage Guard Rail	L.FT.	4,013
Shoulder Build-up (Milled AC)	L.FT.	64,010
Bituminous Tack Coat & Fog Coat	TON	144
Asphalt Binder (PG 70-10)	TON	1,555
Asphaltic Concrete Friction Course(Asphalt Rubber)	TON	2,824
Asphalt Rubber Material (For AR-ACFC)	TON	255
Asphalt Concrete(3/4" Mix)(End Product)(Sp. Mix)	TON	29,340
Structural Concrete (Class S)(F'C = 4,000)	CU.YD.	30
Reinforcing Steel (Epoxy Coated)	LB.	2,120
Temporary Concrete Barrier(Inst. & Removal)	L.FT.	1,220
Temporary Impact Attenuators (Inst. & Removal)	EACH	2
Temporary Painted Marking (Stripe)	L.FT.	22,650
Temporary Concrete Barrier (In Use)	L.FT./Day	18,300
Temporary Impact Attenuators (In-Use)	EACH/Day	30
Truck Mounted Attenuator	EACH-DAY	2
Flagging Services (Civilian)	HOURL	1,168
Delineator (M-25) (Single or Double)	EACH	104
Pavement Marking (Thermoplastic)(W & Y)	L.FT.	132,300
Permanent Pavement Marking (Painted)(W & Y)	L.FT.	89,100
Pavement Marker (Raised Type C, D & G)	EACH	124

Pavement Marker (Recessed Type C & H)	EACH	2,470
Seeding (Class II)	ACRE	20
Guard Rail, W-Beam, Single Face	L.FT.	4,000
Guard Rail (Nested Steel W-Beam)	L.FT.	263
Thrie-Beam Guard Rail Transition System	EACH	8
Embankment Curb	L.FT.	2,960
Contractor Quality Control	L.SUM	1
Construction Surveying And Layout	L.SUM	1
Ground-In Rumble Strip (12 Inch)	L.FT.	56,600

The time allowed for the completion of the work included in this project will be 130 working days.

The Arizona Department of Transportation hereby notifies all bidders that pursuant to this advertisement for bids, Disadvantaged Business Enterprises will be afforded full opportunity to submit bids in response to this solicitation and will not be discriminated against on the grounds of race, color, sex, or national origin in consideration for an award.

Project plans, special provisions, and proposal pamphlets may be purchased from Contracts and Specifications Section, 1651 W. Jackson, Room 121F, Phoenix, AZ 85007-3217, (602) 712-7221. Plans and bidding documents should be available for sale to bidders within one week following the advertisement for bids. The cost is \$30.00, payable at time of order by cash, check or money order. Please indicate whether a bid proposal package or a subcontractor/supplier set is desired. An additional fee of \$5.00 will be charged for each set of Special Provisions requested which is not accompanied by the purchase of a related set of project plans. Checks should be made payable to the Arizona Department of Transportation. No refund will be made for plans and specifications returned. We cannot guarantee mail delivery.

This project is eligible for electronic bidding.

Cross sections and/or earthwork quantity sheets, if available, may be ordered from the Control Desk of Roadway Design Section at (602) 712-8667. Orders must be placed at least five days prior to bid opening to insure availability. Documents may be picked up and paid for at Contracts & Specifications Section.

No contracting firm will be issued a proposal pamphlet until it has become prequalified. The Application for Contractor Prequalification shall be filed at least 15 calendar days prior to the bid opening date. The Application may be obtained from Contracts and Specifications Section.

No award will be made to any contractor who is not a duly licensed contractor in accordance with Arizona Revised Statutes 32-1101 through 32-1170.03.

All labor employed on this project shall be paid in accordance with the minimum wage rates shown in the General Wage Decision. These rates have been determined in accordance with the requirements of the law and issued by the Secretary of Labor for this project. The wage scale is on file in Contracts and Specifications Section and copies may be obtained at all reasonable times.

A proposal guaranty in the form of either a certified or a cashier's check made payable to the State Treasurer of Arizona for not less than ten percent of the amount of the bid or in the form of a surety (bid) bond for ten percent of the amount of the bid shall accompany the proposal.

Surety (bid) bonds will be accepted only on the form provided by the Department and only from corporate sureties authorized to do business in Arizona.

Proposal pamphlets shall be submitted only in the envelope provided by the Department to:

Arizona Department of Transportation
Intermodal Transportation Division
Contracts and Specifications Section
1651 West Jackson Street, Room 121F
Phoenix, Arizona 85007-3217

Sealed bids will be received until the hour indicated and then publicly opened and read. No bids will be received after the time specified.

Engineering Specialist:	Sarker Rahman	(602) 712-8262
Construction Supervisor:	Joe Schwer	(928) 432-4936

BARRY CROCKETT,
Engineer-Manager
Contracts & Specifications Section

SR: U:\Word\ADV_H6566
11/14/2007