

Arizona Department of Transportation

Transportation Technology Group Freeway Management System Design Guidelines



August 2007
ADOT Project #05-30
TRACS No. H6662 01D
Project No. S-101-B-304
Previously Published 1989, 1994, 1999, and 2002



PAGE INTENTIONALLY LEFT BLANK



CONTRIBUTIONS AND ACKNOWLEDGEMENTS

The *Arizona Department of Transportation (ADOT) Freeway Management System (FMS) Design Guide 2007* is the result of the coordinated efforts of many individuals, groups, research organizations, and government agencies. The guide was prepared for ADOT by *Transcore ITS, LLC*. Preparation of the document was accomplished through the efforts of the following groups and individuals:

ADOT FMS DESIGN GUIDELINE CONTRIBUTORS:

- Debra Bieber Barker, ADOT Transportation Technology Group (TTG) — Project Manager
- Tim Wolfe, ADOT TTG
- Alicia Bayron, ADOT Phoenix Construction District (PCD)
- Girgis Girgis, ADOT PCD
- Alan Hansen, Federal Highway Administration (FHWA)
- Al Kattan, ADOT PCD
- Glenn Jonas, ADOT TTG
- Mani Kumar, ADOT TTG
- Judith Lochner, ADOT PCD
- Jon Lovell, ADOT TTG
- Chuck McClatchey, ADOT Phoenix Maintenance District (PMD)
- Richard Murphy, ADOT Contracts and Specifications
- Jerry Pfiefer, ADOT TTG
- Farzana Yasmin, ADOT TTG
- Robert Alcala, R.A.Alcala, Inc.
- Ron Andrada, Utility Vault, Inc.
- David Chambers, TransCore
- Tom Dooley, FSI, Inc.
- Bruce Farmer, Contractors West, Inc.
- Christie Hall, HanMar Energy, Inc.
- Michael Marum, TransCore- Project Manager
- Ronald Mikalson, TransCore – Principal Author
- John Prowse, Lee Engineers, Inc.
- Marshall Riegel
- Justin Siler, Han Mar Energy, Inc.,
- Richard Semer, R.J.Engineering, Inc.
- Michael Wendtland, ITS Engineers and Constructors, Inc.



PAGE INTENTIONALLY LEFT BLANK

-

Table of Contents

Chapter 1	Introduction	1-1
1.1	Purpose of the Freeway Management System Design Guideline.....	1-1
1.1.1	History of the FMS Design Guide	1-2
1.1.2	FMS Goals and Objectives	1-2
1.1.3	Concept of Communications	1-3
1.1.4	Using this FMS Design Guide with Other Documents	1-4
1.1.5	Definitions	1-5
Chapter 2	Freeway Management System Elements	2-1
2.1	Evolution of FMS Design	2-1
2.2	Mainline System.....	2-2
Chapter 3	Incorporated Freeway Management System Infrastructure Components.....	3-1
3.1	FMS Infrastructure with a Roadway Project	3-1
3.2	FMS Infrastructure Stand-Alone Projects.....	3-2
3.3	Emerging Technology	3-3
Chapter 4	Communications Trunk Conduit System.....	4-1
4.1	Purpose	4-1
4.2	Position of Trunkline within Freeway Right-of-Way	4-1
4.3	Trunkline Conduit Array & Layout.....	4-1
4.3.1	Conduit Array: Three 3-Inch Conduits.....	4-2
4.3.2	Conduit Layout	4-2
4.4	Trunk Conduit Co-Location with Lighting Power Conduits.....	4-8
4.5	Materials - Conduits	4-8
4.5.1	Conduit Connections at Communications Nodes and FMS Segment End Points.....	4-8
4.5.2	Conduit Materials and Construction Methods	4-8
4.5.3	Conduit Trenching and Backfill.....	4-10
4.5.4	Conduit Below Pavement and on Structure.....	4-14
4.5.5	Horizontal Directional Drilling (HDD)	4-20
4.6	Materials - Innerducts	4-20
4.7	Pullboxes.....	4-22
4.7.1	Pullbox Types	4-22
4.7.2	Co-Locating Lighting No. 7 Pullboxes with FMS Trunkline Pullboxes.	4-30
4.7.3	Cable Labeling at Pullboxes	4-32
4.7.4	Fiber-optic Cable Installation Sequential Reports	4-33
Chapter 5	Mainline Detector System	5-1
5.1	Overview of Detection Technology.....	5-1
5.1.1	New Installations	5-1
5.1.2	Retrofit Projects	5-1

5.1.3 Loop Detector Requirements	5-2
Chapter 6 Equipment Cabinets	6-1
6.1 Equipment Cabinet Location.....	6-1
6.1.1 Ramp Metering Cabinets	6-2
6.1.2 Other Equipment Cabinets: CCTV, DMS, Mainline Traffic Monitoring.....	6-2
6.2 Equipment Cabinet Foundation.....	6-2
6.2.1 Foundation Enhancements for Fiber-Optic Cable Connectivity	6-2
6.3 Equipment Cabinet Power & Surge Protection	6-5
6.3.1 Transformer Cabinet Power Disconnect.....	6-5
Chapter 7 Freeway Dynamic Message Signs.....	7-1
7.1 Master Planning of DMS Locations	7-1
7.2 Longitudinal Placement of Freeway DMS.....	7-1
7.3 Lateral Placement of Freeway DMS.....	7-2
7.4 Freeway DMS Controller Cabinet Placement	7-5
7.4.1 New Installations	7-5
7.4.2 Legacy Installations	7-5
7.5 DMS Cabinet Power, CommunicationCPC, and Conduits	7-6
Chapter 8 Closed-Circuit Television (CCTV)	8-1
Chapter 9 Communication Nodes and Node Buildings.....	9-1
9.1 Node Buildings.....	9-1
Chapter 10 Fiber Outside Plant Design and Modeling.....	10-1
10.1 OSP Model.....	10-1
10.1.1 Fiber Splice Tables.....	10-2
10.2 OSP Software	10-8
Chapter 11 Testing	11-1
11.1 Original Testing Requirements	11-1
11.2 Discontinued Tests for Established Technology	11-1
11.3 Required FMS Testing in Current Practice	11-2
11.3.1 Stand Alone Test.....	11-2
11.3.2 Subsystem Acceptance Test (SST)	11-2
11.3.3 System Acceptance Test (SAT)	11-2

List of Tables

Table 1.1 ADOT Regional Connectivity Networks	1-3
Table 1.2 Acronyms	1-5
Table 4.1 Trench Conduit Alignment Device and Backfill Options	4-11
Table 4.2 Ramp Conduit Crossing Cases	4-18
Table 4.3 Destination Labeling Strategy	4-33
Table 10.1 OSP Model Description	10-2
Table 10.2 Translating Data	10-8



PAGE INTENTIONALLY LEFT BLANK

List of Figures

Figure 2.1 Typical Crossroad Interchange.....	2-3
Figure 4.1 Crossroad Interchange Conduit Installation.....	4-4
Figure 4.2 Crossroad Interchange Conduit Locations	4-5
Figure 4.3 Conduit Installation on One Side of Freeway	4-6
Figure 4.4 Trunk Line Trench Configurations.....	4-7
Figure 4.5 FMS Trunkline Trench Configuration CLSM Option	4-12
Figure 4.6 FMS Conduit Installation at Undercrossing Bridge Structure	4-15
Figure 4.7 Conduit Transition at Bridges	4-16
Figure 4.8 Conduit Attachment to Bridge	4-17
Figure 4.9 Ramp Conduit Crossings	4-19
Figure 4.10 FMS Number 7 Pullbox with Extension	4-24
Figure 4.11 Number 9 Pullbox Conduit Routing.....	4-27
Figure 4.12 Number 9 Pullbox Torsion Assist Cover	4-29
Figure 4.13 Roadway Lighting No. 7 Pullbox	4-31
Figure 5.1 Loop Detector.....	5-4
Figure 6.1 Cabinet Dooley Sump Detail	6-3
Figure 6.2 Cabinet Fan Out Kit and Fiber Parch Mounting Bracket Detail	6-4
Figure 6.3 Transformer Cabinet Power Disconnect	6-6
Figure 7.1 Freeway Dynamic Message Signs	7-3
Figure 7.2 Freeway Dynamic Message Sign and Catwalk Elevator	7-4
Figure 8.1 Closed Circuit Television Typical Pole and Cabinet.....	8-3
Figure 9.1 – Typical Node Building Elevation	9-2
Figure 10.1 Level 1 Fiber Optic Communication System-wide Level.....	10-3
Figure 10.2 Level 2 Fiber Optic Communication Typical Cable Schematic.....	10-4
Figure 10.3 Level 3 Fiber Optic Communication Typical Cable Schematic.....	10-5
Figure 10.4 Level 4 Fiber Optic Communication Typical Cable Segment	10-6
Figure 10.5 Level 5 Fiber Optic Communication Single Splice Level	10-7



PAGE INTENTIONALLY LEFT BLANK