

**ITEM 7360161 – POWER SUPPLY (BATTERY BACKUP)(DEPARTMENT  
FURNISHED)**

**SECTION 736 – HIGHWAY AND SIGN LIGHTING**

**736-2.03 Load Center Cabinets:** is modified to add:

**(A) Un-interruptible Power Supply System (UPS)**

Uninterruptible Power Supply System (UPS) unit shall be Department Furnished. The contractor shall install the UPS unit per the manufacturers requirements.

**736-4 METHOD OF MEASUREMENT:** of the Standard Specifications is modified to add:

Un-interruptible Power Supply Systems (UPS) will be measured as a unit for each type of cabinet installed.

**736-5 BASIS OF PAYMENT**

Basis of Payment of the Standard Specifications is revised to read:

The accepted quantities of Un-interruptible Power Supply Systems (UPS), measured as provided above, will be paid for at the contract unit price each, for assembling and installing the Department Furnished cabinets designated in the bidding schedule which price shall be full compensation for the work, complete in place, as described and specified herein and on the plans, including service terminal boxes, breaker panels, foundations, conduit, elbows, anchor bolts, clearance pad, auxiliary signal controls, external logic modules, batteries and all other components necessary to provide a complete functional assembly for controlling the operation and timing of traffic control signals.