

## **VIDEO DETECTION SYSTEM (X-Cameras) (Department Furnished)**

### **SECTION 735 DETECTORS:**

**735-2.01 Vehicle Detectors:** is modified to add:

#### **(E) Video Detection:**

Video detection cameras, mounting brackets, controller cabinet panels, lightning protection, power and video cables, end connectors, and modules shall be Department furnished.

**735-3 Construction Requirements:** of the Standard Specifications is modified to add:

#### **(G) Video Detection:**

Video detection video cables shall run unspliced from base of pole or adjacent pull box, wherever the convenience splice occurs, to the controller cabinet.

Video detection video and power cables shall be clearly tagged and marked in each pull box they pass through, designating the direction, phase or corner served.

**735-4 Method of Measurement:** The first paragraph of the Standard Specifications is revised to read:

Video detection system will be measured as a lump sum for the video detection system, installed.

**735-5 Basis of Payment:** The first paragraph of the Standard Specifications is revised to read:

The video detection system, measured as provided above, will be paid for at the contract price for the video detection system installed, complete in place, which price shall be full compensation for the work described herein and on the project plans.