

**ITEM - REMOVAL OF UNSUITABLE MATERIAL**

The subgrade material from Station \_ + \_ to Station \_ + \_ that does not meet the subgrade acceptance chart shall be overexcavated to a depth of 3 feet below finished subgrade elevation and replaced with \*.

DESIGNER:

- \* Coordinate with Geotechnical Services for concurrence on locations and replacement material type.